



# Lunar Contour Crafting – A Novel Technique for ISRU-Based Habitat Development

Behrokh Khoshnevis – University of Southern California

Melanie P. Bodiford, Kevin H. Burks, Ed Ethridge, & Dennis Tucker – NASA/Marshall Space Flight Center

Won Kim – NASA/Jet Propulsion Laboratory

Houssam Toutanji – University of Alabama in Huntsville

Michael R. Fiske – Morgan Research Corporation

Paper No. AIAA-2005-XXXX

Presented To:

AIAA 43<sup>rd</sup> Aerospace Sciences Meeting & Exhibit

Reno, NV

January 11, 2005

# Habitat Structures - Introduction

- Habitat Structures at MSFC is one element of the In-Situ Fabrication and Repair (ISFR) Program
  - ISFR develops technologies for fabrication, repair and recycling of tools, parts, and habitats/structures using in-situ resources
  - ISRU-based habitat structures are considered Class III (iaw NASA 1997 Habitat Development Roadmap (Cohen & Kennedy)) and apply primarily to Spirals 3 (Moon) and 5 (Mars)
- Habitat Structures Purpose:
  - Develop Lunar and/or Martian habitat structures for manned missions that maximize the use of in-situ resources to address the following agency topics:
    - Bioastronautics Critical Path Roadmap (BCPR, Rev. E)) risks
      - Risks 31-35 (Radiation Health) , 43-44 (ALS) & 49 (SHFE)
    - Strategic Technical Challenges defined in H&RT Formulation Plan, v. 3.0
      - Margins & Redundancy
      - Reusability
      - Modularity
      - Robotic Networks
      - Space Resource Utilization
      - Autonomy
      - Affordable Logistics Pre-positioning




# Habitat Structures - Introduction

- Habitat Structures – Top-Level Requirements
  - Support a pressurized (shirtsleeve) environment for the crew
  - Protect the crew from a worst case radiation (GCR & SPE) exposure
  - Protect the crew from micrometeorites and exhaust plumes
  - Initially, be able to be fabricated in advance of a manned crew so as to provide immediate protection (semi-autonomous construction)
  - Early, achievable, and visible milestones and successes are required
  - Development should be evolutionary and scalable
  - Present a psychologically/ergonomically compatible living environment for the crew
  - Maximize utilization of in situ resources


# Habitat Structures - Interfaces

## Crew




Radiation Shielding  
Shelter and Storage  
Hermetic Atmospheric Environment  
Assembly, maintenance and repair support  
Micro-meteorite hit protection  
Exhaust Plume protection

## Vehicle




-Transportation of equipment  
upmass/upvolume  
-Temporary Shelter  
-In-flight habitat materials development

## Robotics



Semi-autonomous Construction  
Scouting: exploration of resources  
Materials Sampling  
Information Gathering: locations, scheduling, prioritization


## ISRU



Feedstock for fabrication and repair materials  
Regolith by-products (glass, metals, thin films, etc.

## Ground Ops

Operations Management &  
Decision Support  
Exploration Planning  
In-Situ feedback analysis




## Spiral "N" Applications

-Technology Development for Spiral "N" Applications  
-Technology Maturation/Extension



## ECLSS

ALS  
EVA  
Power  
Cooling  
Heating



## Logistics


Provisions  
Parts and Supplies






# Habitat Structures – Construction Products

Raw Regolith




Blocks




Glass  
Products



Reinforced  
Concrete




Deployable Metal  
Structures




Thin Films/  
Inflatables




# What is Contour Crafting?



- Developed at USC, CC is the application of layered fabrication (also known as solid freeform fabrication or rapid prototyping to construction, particularly with concrete
- Computer-controlled, CC delivers superior surface finish and accurate planar or complex geometries
- Terrestrial applications for low income and Army field housing



- Vertical slope can be changed (domed structures)
- Utilities and/or radiation-shielding materials can be incorporated
- System has been demonstrated at a subscale level, utilizing batch processing



- Can envision large gantry system or multiple robots constructing large-scale terrestrial facilities
- High degree of automation lends CC to other planetary applications



# Elements of Lunar Contour Crafting


- Process Development
  - USC, MSFC
- Robotic Operations for Lunar Construction
  - JPL, USC, MSFC
- Concrete Development
  - UAH, MSFC
- Glass Reinforcement Development
  - MSFC
- Integrated Testing
  - MSFC, USC, JPL, UAH






# Process Development




- Refinement of nozzle, top and side trowel materials and configuration
- Refinement of ability to generate non-orthogonal surfaces (side trowel orientation control)
- Incorporation of integrated flow start/stop capability
- Variable-position nozzle for tight inside corners
- Integrated cleaning system



- Three-dimensional head movement, 6 DOF delivery
- Continuous processing vs batch processing
- Incorporation of utilities such as:
  - Electrical
  - Plumbing
  - Radiation shielding materials



# Infrastructure Support




- Structural reinforcement can be mixed into concrete (glass fibers) or installed during fabrication
- Electrical and plumbing components can be integrated into wall (better on ID for surface applications)
- Radiation shielding components can be integrated into wall, or on either surface



# Robotic Operations for Lunar Construction


- Robotic configurations include gantry system and/or multiple, independently controlled robots
- System can be designed for mobility in the event that crews must change habitat locations
- Telescoping and/or foldable beams can be used for main cross beam, guide rails, and vertical supports
- Proximity controls can be incorporated for later structures development with a manned presence
- Completely autonomous control on the Moon must be demonstrated in order to be a successful tech demo for future Mars applications (time delay)





# Concrete Development


- 1994 STS GAS Can experiment prepared traditional concrete samples with mixed results
- Techniques include:
  - Wet-mix method
  - Dry-mix/Steam Injection (DMSI)
  - Waterless Regolith Mix (WRM)



	Compressive Strength, mPa	Tensile Strength, mPa
LRS/Sulfur Mix	62	7.4
LRS/Portland Cement	35	2.5


- ISFR effort focused on development of "waterless" concrete
- Sulfur-based concrete feasible:
  - Sulfur readily available
  - Good mechanical properties
  - Rapid setting
  - High chemical resistance
  - Low water permeability

- Constraints include:
  - Volume change/softening of S at 96°C
  - Combination of low temperature and low pressure on S sublimation
    - Effect of thermal cycles on strength
- Current research includes:
  - Additions of Dicyclopentadiene to improve strength
  - Effects of glass fiber additions on strength





# Glass Reinforcement Development

- Lunar regolith is comprised of up to 80% glassy materials, depending on regolith "maturity"
- Mechanical properties of lunar-derived glass are expected to be significantly higher than terrestrial glass, based on lack of water during glass formation
- Current work includes:
  - Use of solar-powered furnace to melt LRS, fabricate glass beads and/or fibers
  - Evaluation of additives required to tune optical properties of LRS-derived glass
- Applications for glass products include:
  - electrical and thermal insulation
  - braided cables
  - reinforcement in structural materials
  - struts
  - compression members in tensegrity structures
  - optical elements




(COURTESY UC E





## Test Status



- Currently modifying prototype hardware by:
  - Addition of limit switches
  - Addition of "home" or "stop" position
  - Addition of a third axis of motion to aid in development of more complex shapes
  - Software upgrades
  - Use of LRS-based concrete
  - Addition of capability for continuous processing for future operations
  - Addition of solenoid "shutter" and pressure relief for stop/start operations and air purging of system






# ISFR Habitat Structures Capability Evolution Roadmap

**Current SOA:**  
-Lots of 10-20 yr old Studies  
-Limited experience w/Lunar-based concrete, blocks or glass  
-Few applications of space-based inflatables



**Project Formulation (6/04 – 6/05)**



**Continuous Technology Development**

- Lunar soil (regolith) is well characterized, but from limited locations (Apollo, Luna, Surveyor)
- Probable South Pole location of Moon base is essentially uncharacterized
- Lack of large quantities of high quality Lunar Regolith Simulant (LRS)
- Design must support high tensile loads due to pressurized environment – habitat is a pressure vessel!
- Pre-manned mission construction requires complex robotics and teleoperations
- Integration of utilities and radiation shielding materials
- Configuration-specific technical challenges, for example:
  - Reinforced Concrete
    - Extruded in place vs pre-cast, pre-stressed
    - Steel vs glass rod reinforcement
    - Water-based vs waterless concrete
    - Hermeticity





## Near-Term Development Activities

- Lunar regolith simulant characterization
  - JSC-1 (NASA/JSC)
  - JPT-1890 (Jensan Scientific)
- Concrete development/testing
  - Sulfur & LRS-based concrete testing in work
    - Significant improvements in tensile & compressive strength over Portland cement-based concrete
  - Effects of simulant on materials properties to be evaluated
  - Testing with prototype Contour Crafting system in MDL
- Compacted block development/testing
  - Binderless compacted JSC-1 LRS block did not hold together
  - Evaluating potential binders
- Radiation shielding modeling/testing of candidate configurations
- Evaluation of all technologies with respect to acceptance criteria (being defined), including TRL and RD<sup>3</sup> assessment
- Definition of technology exit criteria